



WHEELCHAIR COMPLIANCE

- 1 - MOVING AROUND OUTSIDE : SEE GROUND FLOOR PLAN
- 2 - USING OUTDOOR SPACES : SEE GROUND AND PLAN FOR EXTERNAL DOOR AND REFUSE APPROACH/ACCESSIBILITY. BALCONY DOORS MEET CRITERIA AS DEMONSTRATED BELOW.
- 3 - APPROACHING THE HOME: COMMUNAL CORRIDORS AND LIFTS MEET CRITERIA AS DEMONSTRATED BELOW.
- 4 - NEGOTIATING THE ENTRANCE DOOR, INCLUDING COMMUNAL DOORS: SEE GROUND FLOOR PLAN.
- 5 - ENTERING AND LEAVING, DEALING WITH CALLERS: WHEELCHAIR TRANSFER AND STORAGE IS PROVIDED AS DEMONSTRATED BELOW.
- 6 - NEGOTIATING THE SECONDARY DOOR: DOORS MEET CRITERIA AS DEMONSTRATED BELOW.
- 7 - MOVING AROUND INSIDE / STORING THINGS: ALL PASSAGEWAYS AND INTERNAL DOORS MEET CRITERIA AS DEMONSTRATED BELOW.
- 8 - MOVING BETWEEN LEVELS: NOT RELEVANT
- 9 - USING LIVING SPACES: TURNING CIRCLES AND TRANSFER SPACES PROVIDED TO MEET CRITERIA AS DEMONSTRATED BELOW.
- 10 - USING THE KITCHEN: MENOEUVERING MEETS CRITERIA AS DEMONSTRATED BELOW.
- 11 - USING THE BATHROOM AND SHOWER ROOM. BATHROOM DESIGNED TO MEET CRITERIA AS DEMONSTRATED BELOW.
- 12 - USING BEDROOMS: TURNING CIRCLES AND TRANSFER SPACE PROVIDED TO MEET CRITERIA AS DEMONSTRATED BELOW.
- 13 - OPERATING DOORS: BATHROOM DOORS SHALL OPEN OUTWARDS AND BE CONSTRUCTED TO MEET CRITERIA AS DEMONSTRATED BELOW.
- 14 - OPERATING WINDOWS: WINDOWS IN THE LIVING ROOM WILL HAVE FULL HEIGHT GLAZING. WINDOW CONTROLS WILL BE NO HIGHER THAN 1200mm EXCEPT IN BATHROOMS / KITCHENS WHERE WINDOW DESIGNS WILL ALLOW FOR REMOTE / MECHANICAL ADAPTION TO OPERATE WINDOWS.
- 15 - CONTROLLING SERVICES: SWITCHES, SOCKETS, VENTILATION & SERVICE CONTROLS WILL BE LOCATED BETWEEN 450 & 900mm FROM FLOOR LEVEL.

CODE FOR SUSTAINABLE HOMES

- 17 - (Ene 4) AN ADEQUATE AND SECURE DRYING SPACE IS TO BE PROVIDED TO THE BATHROOM OR BALCONY.
- 18 - (Ene 9) AN AREA IS TO BE PROVIDED FOR A SUITABLE HOME OFFICE



PLANNING

PROJECT				89-93 NEWINGTON CAUSEWAY				panter hudspith architects			
DRAWING				DETAILED UNIT LAYOUT UNIT TYPE B [WHEELCHAIR ACCESSIBLE] (wheelchair compliance incl adapted bathroom)				4-8 Emerson Street, London SE1 9DU t: 020 7633 9425 e: info@panterhudspith.com			
JOB No.				DRAWING No.				REV			
340				P / 162				/			
DO NOT SCALE THIS DRAWING. CHECK ALL DIMENSIONS ON SITE. IF IN DOUBT ASK				SCALE				SIZE			
All information contained in this drawing is sole copy right of Panter Hudspith Architects and is not to be reproduced without their permission.				1:50				A3			